

E - Wood Plus, Inc.
Design Solutions. Prompt Estimates. Detailed Layouts.

114 South Main Street, Cheshire CT 06410 phone: 203-439-9131

Customer:		Job Name:			
Contact:		Date:			
P. O. #		Total Pages:	6		

Disclaimer: This list is for estimating only; exact products, quantities and lengths must be verified by the contractor; exact beam sizes must be verified with an engineer. No guarantee of any kind concerning the accuracy of this estimate is made. The purchaser of this estimate assumes full responsibility for its use.

Combined Material List - see Detailed List for all Notes and Breakdowns

Description	Size	Quantities	Units	Price	Totals
Frame combined					
Sill Sealer at ext. found	6"	7	50' rolls		
Termite Shield	Copperkraft	310	LF		
Plates	2x6 P.T.	362	LF		
Plates	2x6	5010	LF		
Studs&Frame	2x6	18	16		
Studs&Frame	2x6	6	14		
Studs&Frame	2x6	90	12		
Studs&Frame	2x6	1235	10		
Studs&Frame	2x6	43	8		
Plates	2x4 P.T.	198	LF		
Plates	2x4	2104	LF		
Studs&Frame	2x4	170	16		
Studs&Frame	2x4	86	12		
Studs&Frame	2x4	420	10		
Studs&Frame	2x4	8	6		
Plates	2x12 P.T.	112	LF		
Frame	2x12	8	20		
Frame	2x12	5	18		
Frame	2x12	4	16		
Studs	2x12	2	8		
Frame	2x10	16	22		
Frame	2x10	3	20		
Frame	2x10	12	18		
Frame	2x10	139	16		
Frame	2x10	188	14		
Frame	2x10	204	12		
Frame	2x10	27	10		
Frame	2x10	30	8		
Frame	2x8	1	20		
Frame	2x8	17	18		
Frame	2x8	282	16		
Frame	2x8	155	14		
Frame	2x8	52	12		
Studs	2x8	114	10		
Frame	2x8	49	8		
	Page 1				

Frame combined cont					
Subfloor	3/4" T&G	364	4x8		
Panel Adhesive	29OZ	122	tubes		
Furring	1x3	1286	LF		
Plywood for Sweeps	3/4" CDX Ply	298	4x8		
Roof Sheathing	3/4" CDX Ply	159	4x8		
Roof Sheathing (curved)2layer	3/8" CDX Ply	316	4x8	assumed - verify	
Wall Sheathing at Shear Walls	1/2" CDX Ply	46	4x8		
Wall Sheathing	5/8" CDX Ply	218	4x8		
Vapor Barrier	Tyvek	6970	SQ FT		
Beams	1-3/4"x9-1/2" LVL	3	16		
Beams	1-3/4"x9-1/2" LVL	2	14		
Beams	1-3/4"x9-1/2" LVL	1	12		
Beams	1-3/4"x7-1/4" LVL	2	16		
Beams	1-3/4"x7-1/4" LVL	4	14		
Beams	1-3/4"x7-1/4" LVL	1	12		
Beams	1-3/4"x7-1/4" LVL	4	8		
Beams	1-3/4"x14" LVL	2	40		
Beams	1-3/4"x14" LVL	2	30		
Beams	1-3/4"x14" LVL	8	28		
Beams	1-3/4"x14" LVL	6	22		
Beams	1-3/4"x14" LVL	2	20		
Beams	1-3/4"x14" LVL	4	18		
Beams	1-3/4"x14" LVL	4	16		
Beams	1-3/4"x14" LVL	2	14		
Beams	1-3/4"x14" LVL	1	12		
Beams	1-3/4"x14" LVL	3	10		
Beams	1-3/4"x14" LVL	1	6		
Beams	1-3/4"x11-7/8" LVL	2	22		
Beams	1-3/4"x11-7/8" LVL	3	20		
Beams	1-3/4"x11-7/8" LVL	10	18		
Beams	1-3/4"x11-7/8" LVL	6	16		
Beams	1-3/4"x11-7/8" LVL	9	14		
Beams	1-3/4"x11-7/8" LVL	4	10		
Beams	1-3/4"x11-7/8" LVL	2	8		
Posts	5-1/4"x5-1/4" PSL	1	10		
Post	3-1/2"x5-1/4" PSL	1	8		
Posts	3-1/2"x3-1/2" PSL	107	10	or DF - type to verify	
Beam	7"x9-1/4" PSL	1	20		
Beam	7"x9-1/4" PSL	1	10		
Beam	5-1/5"x9-1/4" PSL	1	10		
Beam	5-1/4"x9-1/4" PSL	2	18		
	Page 2				

Frame combined cont					
Rim Joist	1-1/8x11-7/8" LSL	19	16		
Rim Joist	1-1/8x14" LSL	14	16		
Hangers	WPU411.88	1	pcs		
Hangers	WP5.50/11.88	1	pcs		
Hangers	WP411.88	5	pcs		
Hangers	MIU3.12/9	1	pcs		
Hangers	MIU1.56/11	2	pcs		
Hangers	MIT411.88	1	pcs		
Hangers	LUS28	120	pcs		
Hangers	LUS26	6	pcs		
Hangers	LUS210-2	7	pcs		
Hangers	LUS210	68	pcs		
Hangers	ITT411.88	290	pcs	type to verify	
Hangers	ITT3514	120	pcs	type to verify	
Hangers	ITS2.37/11.88	8	pcs		
Hangers	HU48	1	pcs		
Hangers	HHUS410	1	pcs		
Hangers	HGLTV5.514	2	pcs		
Hangers	HGLTV411.88-2	1	pcs		
Simpson	A35	210	pcs		
Simpson Straps	LPT4	500	pcs		
Simpson Straps	MTS30	4	pcs		
Simpson Ties at Ridges	MSTA30	120	pcs		
Simpson Straps	H6	500	pcs		
Simpson Ties at Eaves	H2	150	pcs		
Simpson Ties at Eaves	H10	150	pcs		
Simpson	ECCQ44- SDS 2.5	16	pcs	size to verify	
Simpson	CCQ44- SDS 2.5	21	pcs	size to verify	
Simpson	BC46	2	pcs		
PT Frames combined					
Posts	6x6 P.T.	26	10	assumed for columns	
Posts	4x4 P.T.	1	10		
Posts	4x4 P.T.	9	8		
Frame	2x6 P.T.	30	16		
Frame	2x6 P.T.	11	14		
Frame	2x4 P.T.	76	16		
Frame	2x4 P.T.	18	8		
Frame	2x12 P.T.	2	18		
Frame	2x12 P.T.	18	16		
Frame	2x12 P.T.	16	14		
Frame	2x12 P.T.	57	12		
Frame	2x12 P.T.	107	10		
Frame	2x12 P.T.	58	8		
	Page 4				

PT Frames combined cont					
Frame	2x8 P.T.	32	16		
Frame	2x8 P.T.	1	12		
Frame	2x8 P.T.	7	8		
Hangers	LUS28 Zmax	4	pcs		
Hangers	LUS210 Zmax	202	pcs		
Post Bases	ABU66 Zmax	26	pcs		
Flashings at Wall	Copper	302	LF		
EPDM at deck		240	SQ FT		
Roof Products					
Roof Shingles	18" RC Taper Sawn 5" E	103	Squares	Hand split, medium butt	
Roofing - Hips and Ridges	accessories	230	LFT		
Felt for Roof	15#	9,750	SQ FT		
Ice and Water (eves&valleys)	3x50' rolls	14	rolls		
Cedar Breather		9,750	SQ FT		
Metal Roofs	Copper	140	SQ FT		
Felt for Metal roofs	30#	140	SQ FT		
Flashing	Drip Edge	520	LFT	not shown - verify	
Flashing	Rake Edge	350	LFT	not shown - verify	
Flashing Copper	Valley Flashing	200	LFT		
Flashing Copper	Roof-to-Wall	400	LFT		
Flashing - Lead Copper	at Fireplace	62	LFT		
Ridge Vent		160	LFT		
Soffit Vent at Eaves		390	LFT	not shown - verify	
Exterior Trims combined					
Note: All trims be Azek per e-mail note - verify; some sizes area scaled					
Trims	1x8	1,060	LFT		
Trims	1x6	544	LFT		
Trims	1x4	30	LFT		
Trims	1x14	564	LFT		
Trims	1x12	350	LFT		
Trims	1x10	824	LFT		
Trims	1x Panel	426	SQ FT		
Ext. Casing	1x4	1,060	LFT		
Window Sills		264	LFT		
Drip Cap	5/4x4	120	LFT		
Soffits	1x4 bead bd	3,374	SQ FT		
Crowns	Dykes #195	1,800	LFT		
Crowns	Dykes #194	872	LFT		
Cap Moulding / Crowns	1-1/2"	40	LFT		
Mouldings	1"	80	LFT		
Neck Astragal	1"	6	LFT		
	Page 5				

Exterior Trims comb cont					
Columns w/ Cap & Base	14" Dia Permacast	30	8'9"	verify if load bearing	
Columns w/ Cap & Base	10" Dia Permacast	2	5'3"		
Decking					
Decking	5/4x6 Mahogany	2,610	SQFT	waste included	
Ballustardes	5/4 Sq Mahogany	30	pcs		
Top Rail	1-1/2"x4" Mahogany	16	LF		
Low Wall Cap Rail	1-1/2"x15" Mahogany	16	LF		
Risers	1x6 Mahogany	4	12		
Risers	1x6 Mahogany	3	8		
Siding	Yellow Cedar Shingles	4,400	SQ FT	18" w/ 5-1/2" Exp	
				verify type per e-mail note	
Pergola	Verify Product types				
Beams w/ 2 shaped ends	10x12	1	23	scaled	
Trellis w/ 1 shaped end	2x8	21	15	scaled	
Trellis	2x2	42	11	scaled	
Outdoor shower					
Siding	1x6 T&G	420	SQ FT		
Trims at Shower&Pergola Columns - verify if Cedar / Mahogany					
Column Wraps	1x10	16	10		
Base&Cap Trims	1x6	9	16		
Cap trims	1x4	11	16		
	Page 6				